

ರಾಣಿ ಚನ್ನಮ್ಮ

RANI CHANNAMMA

ವಿದ್ಯಾಸಂಗಮ, ಪಿ.ಬಿ.ರಾಷ್ಟ್ರೀಯ ಹೆದ್ದಾರಿ-4,  
ಭೂತರಾಮನಹಟ್ಟಿ, ಬೆಳಗಾವಿ-591156.



ವಿಶ್ವವಿದ್ಯಾಲಯ

UNIVERSITY

VidyaSangama, P.B.National Highway-04  
Belagavi-591156

**ಕುಲಸಚಿವರ ಕಾರ್ಯಾಲಯ**

ಫೋನ್ ನಂ: 0831-2565242

ಫ್ಯಾಕ್ಸ್ : 0831-2565240

Website: [www.rcub.ac.in](http://www.rcub.ac.in)

E-mail : [rcuregistrar@gmail.com](mailto:rcuregistrar@gmail.com)

ಸಂಖ್ಯೆ: ರಾಚವಿ/ಬೆಳಗಾವಿ/ಕುಸಕಾ/2020-21/3536

ದಿನಾಂಕ:29-11-2020

**ಕೋಟಿಶನ್ ಪ್ರಕಟಣೆ**

Name of Work: Providing Estimation for proposed construction of Cattale Pit @ Rani  
Channamma University Belagavi.

ಉಲ್ಲೇಖ: ಮಾನ್ಯ ಕುಲಪತಿಗಳ ಅನುಮೋದನೆ ದಿನಾಂಕ:29-11-2020.

ಮೇಲಿನ ವಿಷಯಾಂಕಿತ ಕಾಮಗಾರಿಯನ್ನು ಕೈಕೊಳ್ಳಲು ಈ ಪ್ರಕಟಣೆಯೊಂದಿಗೆ Annexure-I ರಲ್ಲಿ ನಮೂದಿಸಿದ Providing Estimation for proposed construction of Cattale Pit @ Rani Channamma University Belagavi. ದುರಸ್ತಿ ಕಾರ್ಯವನ್ನು, ನೊಂದಾಯಿತ ದುರಸ್ತಿದಾರರಿಂದ / ಎಜೆನ್ಸಿಗಳಿಂದ ದರಪಟ್ಟಿಯನ್ನು ಆಹ್ವಾನಿಸಲಾಗಿದೆ. Annexure-I K/Q-1 ರ ನಮೂನೆಯನ್ನು ವಿಶ್ವವಿದ್ಯಾಲಯದ ವೆಬ್‌ಸೈಟ್: [www.rcub.ac.in](http://www.rcub.ac.in) ರಿಂದ ಡೌನ್‌ಲೋಡ್ ಮಾಡಿಕೊಂಡು ದರವನ್ನು ನಮೂದಿಸಿ ಮೊಹರ ಬಂದ ಲಕೋಟಿಯ ಮೇಲೆ "Quotation for Providing Estimation for proposed construction of Cattale Pit @ Rani Channamma University Belagavi." ಎಂದು ನಮೂದಿಸಿ ಕುಲಸಚಿವರು, ರಾಣಿ ಚನ್ನಮ್ಮ ವಿಶ್ವವಿದ್ಯಾಲಯ, ವಿದ್ಯಾಸಂಗಮ, ಬೆಳಗಾವಿ. ಈ ವಿಳಾಸಕ್ಕೆ ದಿನಾಂಕ:07-12-2020 ರ ಒಳಗಾಗಿ ಸಲ್ಲಿಸುವಂತೆ ಕೋರಲಾಗಿದೆ.

ಸಹಿ/-

**ಕುಲಸಚಿವರು**

ರಾಣಿ ಚನ್ನಮ್ಮ ವಿಶ್ವವಿದ್ಯಾಲಯ,  
ಬೆಳಗಾವಿ

ರಾಣಿ ಚನ್ನಮ್ಮ

RANI CHANNAMMA

ವಿದ್ಯಾಸಂಗಮ, ಪಿ.ಬಿ.ರಾಷ್ಟ್ರೀಯ ಹೆದ್ದಾರಿ-4,

ಭೂತರಾಮನಹಟ್ಟಿ, ಬೆಳಗಾವಿ-591156

ಫೋನ್ ನಂ:0831-2565242



ಕಟ್ಟಡ ವಿಭಾಗ

ವಿಶ್ವವಿದ್ಯಾಲಯ

UNIVERSITY

Vidya Sangama, P.B. National Highway-04,

Belagavi-591156

Website: www.rcub.ac.in

Annexure I

K/Q-1

**INVITATION FOR QUOTATION FOR:** Providing Estimation for proposed construction of Cattale Pit @ Rani Channamma University Belagavi.

To,

The Registrar

Rani Channamma University

Belagavi.

Sir,

Sub: Invitation of quotation for Providing Estimation for proposed construction of Cattale Pit @ Rani Channamma University Belagavi.

1. Sealed competitive quotations are invited by the undersigned for the following items.

Sl.No	Particulars	Quantity	Rate+AW-5%	Amount					
1	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines, and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from the edges of excavation with lead upto 50m after breaking of clods complete as per specifications. Specification No. KBS 2.1(a)/2.3.5								
	PWD circle BGM SR 2016-17, Pg No- 5 Item NO 2.4								
	In Hard Soil	Cum							
		1	3.20	3.20	0.60	6.14			
		1	24.00	0.45	0.45	4.86			
		1	12.00	0.45	0.45	2.43			
	<b>Total Qty</b>	Cum				<b>13.43</b>			
2	KSRB 4-1.5: Providing and laying in position plain cement concrete of Mix M20 with OPC@ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.43cum, machine mixed, concrete laid in layers not exceeding 15 ems. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2								
	PWD circle BGM SR2016-17, Pg No- 12 Item NO 4.5								
	Column Footing F-1	Cum	1	12.00	0.45	0.15	<b>0.81</b>		
	<b>Total</b>	Cum					<b>0.81</b>		

3	KSRB 4.2.2 Providing and laying in position reinforced cement concrete of Design Mix M20 with OPC@ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6							
	PWD circle BGM SR 2016-17, Pg No- 12Item NO 4.11							
	Column Footing F-1	Cum	1	3.00	3.00	0.40	3.60	
	<b>Total</b>	<b>Cum</b>					<b>3.60</b>	
4	KSRB 6-1.2 : Providing and constructing burnt brick masonry for basement and superstructure with approved quality of non-modular bricks of standard size of class designation 3.5Newton per sqmm with cement mortar1:8 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2							
	PWD circle BGM SR 2016-17, Pg No- 27 Item NO 6.6							
	Brick Wall	Cum	4	3	0.23	0.60	1.66	
	<b>Total</b>	<b>Cum</b>					<b>1.66</b>	
	<b>NET QUANTITY</b>	<b>Cum</b>					<b>1.66</b>	
5	KSRB 4-6.1: Providing and removing centering, shuttering, strutting, propping etc, and removal of from work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.							
	PWD circle BGM SR 2016-17, Pg No- 16 Item NO 4.28							
	Bed Concrete	sqm	1	12.00		0.20	2.40	
	Coping	sqm	1	12.00		0.30	3.60	
	<b>Total</b>	<b>sqm</b>					<b>6.00</b>	
6	KSRB 4.2.8: Providing and laying in position reinforced cement concrete of design Mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with super plasticisers @31ts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 ems thick, vibrated for all works in ground floor level for roof slabs, staircase, lintels, and beams retaining walls, return walls, walls (any thickness) including attached pilasters, columns, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6							
	PWD circle BGM SR 2016-17, Pg No- 15 Item NO 4.13							
	Coping	sqm	4	3.00	0.23	0.30	0.83	
7	KSRB15-3 : Providing 18mm thick cement plaster in single coat with cement mortar to brick masonry including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.							
	PWD circle BGM SR 2016-17, Pg No- Item NO 15.15							
	Brick Wall	sqm	4	3.00		1.00	12.00	

8	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Fe-500							
	PWD circle BGM SR 2016-17, Pg No- 19 Item NO 4.46.2							
							324.00	
	<b>Total</b>	<b>MT</b>					<b>0.32</b>	
9	Solid Blocks(Concrete 40x20x20cms)-4N/Sqmm							
	PWD circle BGM SR 2016-17, Pg No- I Code No-0391							
	<b>Total</b>	<b>No's</b>					<b>300.00</b>	
							<b>GST 12%</b>	
							<b>TOTAL AMOUNT</b>	

2. Quoted Price:

The Tenderer shall quote for items in the format of quotation attached;

- a. The quotation shall be attached with the specification GST payable by the tenderer
- b. The rates quoted for each item shall be fixed for the duration of the contract and shall not be subject to any adjustment.
- c. Rates for supply of partial quantity of an item is not acceptable.
- d. Corrections if any shall be made by crossing out, initialing, dating and rewriting.

3. Each tenderer must submit only one quotation.

4. Bidder should be enclosed the site visit certificate.

5. Validity of quotations:

The quotation shall remain valid for a period not less than 30 days after the deadline Fixed for submission of quotations

6. Evaluation of quotations:

The Tenderer will evaluate and compare the quotations determined to be substantially Responsive i.e., which are properly signed, and conform to the terms and conditions and specifications in the following manner:

- a. The evaluation will be done including the GST. If the tenderer has not included the GST in his quotation for the item rate, and has also not indicated the rate of GST applicable, the quoted rate will be treated as though it is inclusive of the GST and no extra payment for GST will be made;
- b. The evaluation would be done for all the items put together. The items for which no rates have been quoted would be treated as zero and the total amount would be computed accordingly. The tenderer who has quoted for partial quantity of any one or more item(s) would be treated as non-responsive. Purchaser will award the contract to the responsive tenderer, whose total cost for all the items put together is the lowest..

7. Award of Contract:

- a. The Tenderer will award the contract to the tenderer whose quotation has been determined to be substantially responsive and who has offered the lowest price as per Para 5(b) above.
- b. The Tenderer reserves the right at the time of contract award to increase or decrease the quantities of any or all of the items indicated in para 1 above by 25% without any change in the unit price or any other terms and conditions.
- c. The Tenderer prior to the expiration of the quotation validity period will notify the tenderer whose quotation is accepted to the award of contract. The terms of the accepted offer shall be incorporated in the purchase order.
- d. Normal commercial warranty/guarantee shall be applicable to the supplied goods.
- e. Payment shall be made after the delivery of the goods and their acceptance.
- f. Notwithstanding the above, the Tenderer reserves the right to accept or reject any quotations and to cancel the quotation process and reject all quotations at any time prior to the award of the contract.

You are requested to submit the sealed quotations super scribed on the envelope as "Quotations for repairs of "Providing Estimation for proposed construction of Cattale Pit @ Rani Channamma University Belagavi." due on latest by 3.00pm hours on-07-12-2020.

8. We look forward to receiving your quotations.

Yours Sincerely,

Attachment:

Sd/-

Assistant Executive Engineer  
Rani Channamma University,  
Belagavi.

Telephone No:0831-2565242.